Table 21-1: BEADED PANEL FABRICATION OPERATIONS

40 x 40 PANEL

OPERATION	DIRECT HOURS
STRETCH FORMED PANELS	
• Shear Panel (7075-0)	0.5
• Shear Picture Frame Doublers	0.5
• De-burr	0.5
• Clean	0.5
• Spot-weld Picture Frame to Doublers	3.0
• Form 1st Stage	2.0
• Form 2nd Stage	2.0
• Clean	0.5
• Solution Heat Treatment	0.5
• Form 3rd Stage	2.0
• Rough Trim	0.5
• De-burr	0.5
• Clean	0.5
• Assemble/Age	3.5
• Net Trim	0.5
• Clean	0.5
	18.0
	* 2.0
	20.0
BRAKE-FORMED PANEL (40 x 40)	
• Shear Panel (7075-0)	0.5
• Drill Index Holes (24 places)	2.0
• Blank Cut-outs	2.0
• De-burr	4.0
• Clean	0.5
• Solution Heat Treatment	0.5
• Form Bead	4.0
• Form Closure	4.0
• Straighten	1.5
• Rough Trim	0.5
• De-burr	0.5
• Clean	0.5
• Assemble/Age	3.5
• Net Trim	0.5
• Clean	0.5
	25.0
	* 2.0
	27.0
*** COMMON TO BOTH PANELS (PREPARED DOUBLERS)**	
• Shear Doubler Blanks	0.5
• Blank Doublers	0.5
• De-burr	0.5
• Clean	0.5
	2.0